

Merging Innovation and Excellence®

www.trafficgroup.com

Traffic Engineering ▪ Traffic Data Collection ▪ Transportation Planning

Friendship Heights – Chevy Chase

- Traffic counts and speed studies – March 11 – 17, 2026.
- 85th percentile speeds ok – due to short road links.
- Sign replacements: damaged, cracked, faded, dirty, 7 ft. height
- HAWK Signals – not warranted for full signals.
- Proposed 5 speed humps, removal of bumps.
- Proposed Pavement Marking upgrades, faded and missing.
- Pedestrian walk times at signals. Walk times 3.5 vs 2.5 fps.

Friendship Heights – Chevy Chase

- Streetlight review – 2 overhead lights out 1 Willard & 1 MD 355
- MDSHA and MDOT missing some Crosswalk Thermo. update
- Proposed Redevelopment of the Geico Office Complex.
- TTG - 2 HAWK signals still not warranted.
- Willard Ave at Geico / N. Park Ave Full Signal operation.
- Reviewed Internal Intersection for signals – not warranted.
- Install Bump-outs at Intersections.

Friendship Heights – Recommendations:

- Upgrade signage and pavement markings.
- Install bump-outs with concrete or planters. Prelim cost provided.
- Install 5 humps to discourage cut-thru traffic and slow speeds.
- Flashing Stop Signs.
- New pedestrian Maryland Law signs – must stop for peds.
- Letter to both state and county about crossing times.
- Request lighting repairs.

The Traffic Group

www.trafficgroup.com



pdorr@trafficgroup.com

The Traffic Group®